




* MINIMUM DISTANCE BETWEEN FACE OF EXCAVATION & STRUCTURE TO ALLOW ACCESS TO PLACE GRANULAR FILL & COMPACT

ITEM - DESCRIPTION	REFERENCE No.	QTY REQ'D	WEIGHT EACH (Kg)	REMARKS
1 "H" Pole Timber Baulk	LSTC/STD/PAR/738	1	192.5	Timber Baulk "D" in addition to LSTC/STD/GNA/502
2 Foundation Block	LSTC/STD/PAR/602	2	42	Foundation Block "C" in addition to LSTC/STD/GNA/502
3 M20 Bolts x Length To Suit Pole Diameter	LSTC/STD/GNA/555	2	2.4	M20 Bolts to attach additional Timber Baulk "D" to Foundation
4 M20 Bolts x Length To Suit Pole Diameter	LSTC/STD/GNA/555	2	0.5	M20 Bolts to attach additional Foundation Block "C"
5 Square Flat Washer	LSTC/STD/PAR/619	2	0.1	
6 Square Curved Washer	LSTC/STD/PAR/620	2	0.2	
7 Geotextile Membrane	--	1	--	Place in Bottom of Excavation Prior to Granular Backfill

Total Calculated Weight = 283Kg

GENERAL NOTES:

- ALL STEELWORK TO BE PROTOTYPE CHECK ERECTED PRIOR TO MASS PRODUCTION.
- ALL DIMENSIONS ARE IN MILLIMETRES.
- MATERIAL LIST INDICATES ADDITIONAL ITEMS REQUIRED WHEN "VERY POOR" SOIL CONDITIONS ARE ENCOUNTERED. THESE FOUNDATIONS CAN ONLY BE INSTALLED IN LEVEL GROUND.

TO BE READ IN CONJUNCTION WITH:
 LSTC/STD/GNA/502: 0-5° ANGLE STRUCTURE
 LSTC/STD/GNA/504: MATERIAL LIST
 LSTC/STD/GNA/555: BOLT LENGTH DETERMINATION

- IMPORTANT: REFER TO LSTC/STD/GNA/779 SHEETS 1 TO 4 FOR FOUNDATION DESIGN CRITERIA.

SHT 1 : SOIL CLASSIFICATIONS & POLE EMBEDMENT DETAILS.
 SHT 2 : FOUNDATION DETAILS / STRUCTURE TYPES.
 SHT 3 : FACTORS OF SAFETY.
 SHT 4 : OUTLINE DESIGN FOR "VERY POOR" SOIL FOUNDATIONS.



CLIENT PowerSystems	TITLE ADDITIONAL MATERIAL 0-5° ANGLE STRUCTURE VERY POOR SOIL CONDITIONS	SCALE 1:60 (UNLESS OTHERWISE STATED) DATE 11/05/05 DRAWN R.F. DRAWING NUMBER LSTC/STD/GNA/793	ORIGINAL SIZE A4 CHECKED GS APPROVED PP REV 3	LS TRANSMISSION CONSULTANCY LIMITED Yorkshire House York Road Little Driffield East Yorkshire YO25 5XA 01377 253617
SPECIFICATION OHL-03-132				