



DESCRIPTION SEE SHEET 1 FOR REVISION HISTORY				
REV	DATE	BY	CHKD	APPD

	ITEM - DESCRIPTION	REFERENCE No.	QTY REQ'D	WEIGHT EACH (Kg)	REMARKS
1	Foundation Block	LSTC/STD/PAR/602	2	40	Foundation Block "C" in addition to LSTC/STD/GNA/546 & 547
2	M20 Bolts x Length To Suit Pole Diameter	LSTC/STD/GNA/555	2	0.5	M20 Bolts to attach additional Foundation Block "C"
3	Square Flat Washer	LSTC/STD/PAR/619	5	0.1	
4	Square Curved Washer	LSTC/STD/PAR/620	3	0.1	
5	Geotextile Membrane	--	1	--	Place in Bottom of Excavation prior to Granular Backfill
6	Timber Baulk	LSTC/STD/PAR/601	2	135	Timber Baulk "D" in addition to LSTC/STD/GNA/546 & 547
7	M20 Bolts x Length To Suit Pole Diameter	LSTC/STD/GNA/555	2	2.0	M20 Bolts to attach additional Timber Baulk "D"
Total Additional Calculated Weight = 356Kg					

GENERAL NOTES:

1. ALL STEELWORK TO BE PROTOTYPE CHECK ERECTED PRIOR TO MASS PRODUCTION.
2. ALL DIMENSIONS ARE IN MILLIMETRES.
3. MATERIAL LIST INDICATES ADDITIONAL ITEMS REQUIRED WHEN "VERY POOR" SOIL CONDITIONS ARE ENCOUNTERED.
NOTE ONLY THE 14M POLES REQUIRE FOUNDATION BLOCKS & TIMBER BAULK.
FOUNDATIONS TO BE INSTALLED IN LEVEL GROUND ONLY.

READ IN CONJUNCTION WITH:

LSTC/STD/GNA/814 SHT 1: ADDITIONAL FOUNDATION DETAILS

LSTC/STD/GNA/545, 546 & 547: 4 POLE TERMINAL

LSTC/STD/GNA/548: MATERIAL LIST

LSTC/STD/GNA/555: BOLT LENGTH DETERMINATION

4. IMPORTANT: REFER TO LSTC/STD/GNA/779 SHEETS 1 TO 4 FOR FOUNDATION DESIGN CRITERIA.

SHT 1 : SOIL CLASSIFICATIONS & POLE EMBEDMENT DETAILS.

SHT 2 : FOUNDATION DETAILS / STRUCTURE TYPES.

SHT 3 : FACTORS OF SAFETY.

SHT 4 : OUTLINE DESIGN FOR "VERY POOR" SOIL FOUNDATIONS.

CLIENT PowerSystems		TITLE ADDITIONAL MATERIAL 4 POLE TERMINAL VERY POOR SOIL CONDITIONS SHT 2 OF 2	SCALE 1:60 (UNLESS OTHERWISE STATED)		ORIGINAL SIZE A4		LS TRANSMISSION CONSULTANCY LIMITED  Yorkshire House York Road Little Driffield East Yorkshire YO25 5XA 01377 253617
SPECIFICATION OHL-03-132			DATE 16/05/05		CHECKED GS		
			DRAWN R.F.		APPROVED PP		
			DRAWING NUMBER LSTC/STD/GNA/814		REV 5		