




APPROXIMATE GUIDE FOR SETTING OUT STAY POSITIONS AT VARIOUS GROUND LEVELS


Overall Pole length (m)		12		13		14		15	
Att. Height above ground (m)		9.5		10.5		11.5		12.5	
Height Difference (hd) (m)		X (m)	Y (m)	X (m)	Y (m)	X (m)	Y (m)	X (m)	Y (m)
STAY	3	5.55	3.93	6.37	4.50	7.19	5.08	8.01	5.65
LEVEL	2.5	5.96	4.22	6.78	4.79	7.60	5.36	8.42	5.94
ABOVE	2	6.37	4.50	7.19	5.08	8.01	5.65	8.83	6.22
POLE	1.5	6.78	4.79	7.60	5.36	8.42	5.94	9.24	6.51
DATUM	1	7.19	5.08	8.01	5.65	8.83	6.22	9.65	6.80
LEVEL	0.5	7.60	5.36	8.42	5.94	9.24	6.51	10.06	7.08
	0	8.01	5.65	8.83	6.22	9.65	6.80	10.47	7.37
	0.5	8.42	5.94	9.24	6.51	10.06	7.08	10.88	7.66
	1	8.83	6.22	9.65	6.80	10.47	7.37	11.29	7.94
	1.5	9.24	6.51	10.06	7.08	10.88	7.66	11.70	8.23
	2	9.65	6.80	10.47	7.37	11.29	7.94	12.11	8.52
	2.5	10.06	7.08	10.88	7.66	11.70	8.23	12.52	8.80
	3	10.47	7.37	11.29	7.94	12.11	8.52	12.93	9.09

True Angle 'b' (deg) = 45

Splay Angle 'a' (deg) = 55

xoff (m) = 0.23

yoff (m) = 0.2



NOTE:-

1. SPLAY ANGLE IN PLAN VIEW 'a' = 55°
2. TRUE STAY ANGLE 'b' = 45°
3. 'hd' = MEASURED HEIGHT DIFFERENCE BETWEEN POLE G.L. DATUM AND STAY WIRE SETTING OUT POINT, THIS MUST BE DETERMINED FOR EACH STAY LOCATION BEFORE 'x' AND 'y' SETTING OUT VALUES CAN BE USED.
4. SETTING OUT VALUES ARE FOR GUIDANCE ONLY. 'x' AND 'y' VALUES STATED ARE HORIZONTAL DISTANCES VIEWED FROM ABOVE. TRUE VERTICAL STAY AND SPLAY ANGLES TO BE SITE VERIFIED PRIOR TO INSTALLATION.

$$x' = x_{off} + s'x(\sin a' / \tan b')$$

$$y' = y_{off} + s'y(\cos a' / \tan b')$$