

DESCRIPTION					
FIRST ISSUE					
REV	DATE	BY	CHKD	APPD	
A	14/09/15	JDH	OC	KM	

	ITEM - DESCRIPTION	REFERENCE No.	QTY REQ'D	WEIGHT EACH (kg)	REMARKS
1	Foundation Block	LSTC/STD/PAR/602	2	40	Foundation Block "C" in addition to 15_15229_41 & 42
2	M20 Bolts x Length To Suit Pole Diameter	LSTC/STD/GNA/555	2	0.5	M20 Bolts to attach additional Foundation Block "C"
3	Square Flat Washer	LSTC/STD/PAR/619	5	0.1	
4	Square Curved Washer	LSTC/STD/PAR/620	3	0.1	
5	Geotextile Membrane	--	1	--	Place in Bottom of Excavation prior to Granular Backfill
6	Timber Baulk	LSTC/STD/PAR/601	2	135	Timber Baulk "D" in addition to 15_15229_41 & 42
7	M20 Bolts x Length To Suit Pole Diameter	LSTC/STD/GNA/555	2	2.0	M20 Bolts to attach additional Timber Baulk "D"
Total Additional Calculated Weight = 356Kg					

GENERAL NOTES:

- ALL STEELWORK TO BE PROTOTYPE CHECK ERECTED PRIOR TO MASS PRODUCTION.
- ALL DIMENSIONS ARE IN MILLIMETRES.
- MATERIAL LIST INDICATES ADDITIONAL ITEMS REQUIRED WHEN "VERY POOR" SOIL CONDITIONS ARE ENCOUNTERED.
NOTE ONLY THE 15m POLES REQUIRE FOUNDATION BLOCKS & TIMBER BAULKS.
FOUNDATIONS TO BE INSTALLED IN LEVEL GROUND ONLY.

READ IN CONJUNCTION WITH:

16_15229_51 SHT 1 : ADDITIONAL FOUNDATION DETAILS

15_15229_40/41/42: 4 POLE TERMINAL

15_15229_43: MATERIAL LIST

LSTC/STD/GNA/555: BOLT LENGTH DETERMINATION

- IMPORTANT: REFER TO LSTC/STD/GNA/779 SHEETS 1 TO 4 FOR FOUNDATION DESIGN CRITERIA.

SHT 1 : SOIL CLASSIFICATIONS & POLE EMBEDMENT DETAILS.

SHT 2 : FOUNDATION DETAILS / STRUCTURE TYPES.

SHT 3 : FACTORS OF SAFETY.

SHT 4 : OUTLINE DESIGN FOR "VERY POOR" SOIL FOUNDATIONS.

CLIENT 	TITLE ADDITIONAL MATERIAL 4 POLE TERMINAL VERY POOR SOIL CONDITIONS SHT 2 OF 2	SCALE 1:60 (UNLESS OTHERWISE STATED)	ORIGINAL SIZE A4	LS TRANSMISSION CONSULTANCY LIMITED Yorkshire House York Road Little Driffield East Yorkshire YO25 5XA 01377 253617 
		DATE 14/09/2015	CHECKED OC	
DRAWN JDH		APPROVED KM		
DRAWING NUMBER 16_15229_51		REV A		
SPECIFICATION CUMNOCK - DERSALLOCH ROUTE				