

DESCRIPTION		FIRST ISSUE			
REV	DATE	BY	CHKD	APPD	
A	04/08/15	JDH	OC	KM	

ITEM - DESCRIPTION		REFERENCE NUMBER	QTY REQ'D	WEIGHT EACH (kg)	REMARKS
1	Surge Arrester	N/A	3	N/A	To Suit Project Specification
2	Cable Sealing End	N/A	3	N/A	To Suit Project Specification
3	Crossarm Assy	LSTC/STD/GNA/534	1	882	
4	Wood Pole 15m Long	18_15229_39	2	750	Weight Based on 15m Long Extra Stout Pole
5	Wood Pole 11m Long	18_15229_38	2	550	Weight Based on 11m Long Extra Stout Pole
6	Pole Cap	REF:-	4	N/A	
7	"H" Pole Foundation Brace	LSTC/STD/PAR/603	4	53.4	125x75x12 U.E.A. x 3235 long 4 holes
8	Timber Baulk	LSTC/STD/PAR/601	1	135	
9	Foundation Block	LSTC/STD/PAR/602	2	40	
10	Bolt Set M24 x Length to Suit Pole Diameter	LSTC/STD/GNA/555	6	0.5	BS3692 GR8.8
11	Square Curved Washer	LSTC/STD/PAR/620	7	0.2	
12	Square Flat Washer	LSTC/STD/PAR/619	6	0.1	
13	Insulated Stay Assembly	LSTC/STD/GNA/560	6	N/A	
14	Anti-Split Bolt M20 Length to Suit Pole Diameter	LSTC/STD/GNA/555	4	0.5	
15	Bolt Set M20 x Length to Suit Pole Diameter	LSTC/STD/GNA/555	5	0.5	FDN Bolts for Main Poles
16	OPGW Termination Assembly	LSTC/STD/GNA/758	1	N/A	
17	Stay Attachment Plate	LSTC/STD/PAR/605	2	9.7	
18	125kN Tension Insulator Set	52_15229_04	3	N/A	
19	Cable Guard Back Board	REF:-	1	47.5	Supplied by Cable Contractor
20	Cable Guard Cover Plate	REF:-	2	37.0	Supplied by Cable Contractor
21	Cable Support Crossmember	REF:-	4	31.5	Supplied by Cable Contractor
22	Cable Support Crossmember	REF:-	1	22.5	Supplied by Cable Contractor
23	Surge Arrester Mounting Plate	LSTC/STD/PAR/704	3	26.8	624x456x12 thk plate 10 holes/slots
24	Cable Cleat Support	LSTC/STD/PAR/703	3	4.0	50x50x5 E.A. x 938 long and 152x76x5 thk plate (fabricated)
25	Sealing End Support	LSTC/STD/PAR/702R	3	12.6	125x75x10 U.E.A. x 838 long 7 holes
26	Sealing End Support	LSTC/STD/PAR/702L	3	12.6	125x75x10 U.E.A. x 838 long 7 holes
27	Channel Supports	LSTC/STD/PAR/701	6	59.0	125x65x15 kg/m PFC x 4910 lg 12 holes
28	Cable Terminal Support Channel	LSTC/STD/PAR/700	1	83.5	125x65x15 kg/m PFC x 4910 lg 18 holes & 2x 12thk welded lugs
29	Single Cable Cleat	TBA	9	N/A	
30	Trefoil Cable Cleat	TBA	5	N/A	
31	Sealing End Mounting Bolts	TBA	12	N/A	
32	Surge Arrester Mounting Bolts	TBA	12	N/A	
33	Tee Off Clamp	TBA	3	N/A	
34	Cable Guard Fixings	REF:-	20	0.1	Supplied by Cable Contractor
35	Bolt Set M16x45	BS3692 GR8.8	50	0.2	C/W Nut, Palnut, & Flat Washer

CONTINUED ON SHEET 2

CLIENT		TITLE	MATERIAL LIST - 0° ENTRY / TERMINAL 4 POLE STRUCTURE (SHEET 1 OF 2)	SCALE		N.T.S	ORIGINAL SIZE	A4	LS TRANSMISSION CONSULTANCY LIMITED Yorkshire House York Road Little Driffield East Yorkshire YO25 5XA 01377 253617
				DATE		04/08/15	CHECKED	OC	
				DRAWN		JDH	APPROVED	KM	
				DRAWING NUMBER		19_15229_43	REV	A	
				SPECIFICATION		CUMNOCK - DERSALLOCH ROUTE			

