

DESCRIPTION		FOR ISSUE			
REV	DATE	BY	CHKD	APPD	
9	03/08/07	JR	GS	PP	

ITEM	DESCRIPTION	REFERENCE NUMBER	QTY REQ'D	WEIGHT EACH (kg)	REMARKS
1	Surge Arrester	N/A	3	N/A	To Suit Project Specification
2	Cable Sealing End	N/A	3	N/A	To Suit Project Specification
3	Crossarm Assy	LSTC/STD/GNA/534	1	882	
4	Wood Pole 14m Long	LSTC/STD/PAR/710	2	700	Weight Based on 14m Long Extra Stout Pole
5	Wood Pole 10m Long	LSTC/STD/PAR/709	2	500	Weight Based on 10m Long Extra Stout Pole
6	Pole Cap	REF:	4	N/A	
7	"H" Pole Foundation Brace	LSTC/STD/PAR/603	4	53.4	125x75x12 U.E.A. x 3235 long 4 holes
8	Timber Baulk	LSTC/STD/PAR/601	1	135	
9	Foundation Block	LSTC/STD/PAR/602	2	40	
10	Bolt Set M24 x Length to Suit Pole Diameter	LSTC/STD/GNA/555	6	0.5	BS3692 GR8.8
11	Square Curved Washer	LSTC/STD/PAR/620	7	0.2	
12	Square Flat Washer	LSTC/STD/PAR/619	6	0.1	
13	Insulated Stay Assembly	LSTC/STD/GNA/560	6	N/A	
14	Anti-Split Bolt M20 Length to Suit Pole Diameter	LSTC/STD/GNA/555	4	0.5	
15	Bolt Set M20 x Length to Suit Pole Diameter	LSTC/STD/GNA/555	5	0.5	FDN Bolts for Main Poles
16	OPGW Termination Assembly	LSTC/STD/GNA/758	1	N/A	
17	Stay Attachment Plate	LSTC/STD/PAR/605	2	9.7	
18	125kN Tension Insulator Set	LSTC/STD/GNA/564	3	N/A	
19	Cable Guard Back Board	REF:-	1	47.5	Supplied by Cable Contractor
20	Cable Guard Cover Plate	REF:-	2	37.0	Supplied by Cable Contractor
21	Cable Support Crossmember	REF:-	3	31.5	Supplied by Cable Contractor
22	Cable Support Crossmember	REF:-	1	22.5	Supplied by Cable Contractor
23	Surge Arrester Mounting Plate	LSTC/STD/PAR/704	3	26.8	624x456x12 thk plate 10 holes/slots
24	Cable Cleat Support	LSTC/STD/PAR/703	3	4.0	50x50x5 E.A. x 938 long and 152x76x5 thk plate (fabricated)
25	Sealing End Support	LSTC/STD/PAR/702R	3	12.6	125x75x10 U.E.A. x 838 long 7 holes
26	Sealing End Support	LSTC/STD/PAR/702L	3	12.6	125x75x10 U.E.A. x 838 long 7 holes
27	Channel Supports	LSTC/STD/PAR/701	6	59.0	125x65x15 kg/m PFC x 4910 lg 12 holes
28	Cable Terminal Support Channel	LSTC/STD/PAR/700	1	83.5	125x65x15 kg/m PFC x 4910 lg 18 holes & 2x 12thk welded lugs
29	Single Cable Cleat	TBA	9	N/A	
30	Trefoil Cable Cleat	TBA	4	N/A	
31	Sealing End Mounting Bolts	TBA	12	N/A	
32	Surge Arrester Mounting Bolts	TBA	12	N/A	
33	Tee Off Clamp	TBA	3	N/A	
34	Cable Guard Fixings	REF:-	20	0.1	Supplied by Cable Contractor
35	Bolt Set M16x45	BS3692 GR8.8	50	0.2	C/W Nut, Palnut, & Flat Washer

CONTINUED ON SHEET 2

CLIENT PowerSystems	TITLE MATERIAL LIST - 0° ENTRY / TERMINAL 4 POLE STRUCTURE (SHEET 1 OF 2)	SCALE (UNLESS OTHERWISE STATED)	ORIGINAL SIZE A4	LS TRANSMISSION CONSULTANCY LIMITED Yorkshire House York Road Little Driffield East Yorkshire YO25 5XA 01377 253617
		DATE 26/01/05	CHECKED GS	
DRAWN R.T.J		APPROVED PP		
DRAWING NUMBER LSTC/STD/GNA/548		REV 9		
SPECIFICATION OHL-03-132				

