




'H' IN LINE
SUPPORT
(TYPE 1)



'H' ANGLE
SUPPORT
(TYPE 2)



SLACK SPAN 'H'
TERMINAL SUPPORT
(TYPE 3)

POLE LENGTH (m)	DIM 'A' (m)	DIM 'B' (m)	DIM 'C' (m)
UP TO 11.5	1.2	1.4	6.0
12.0 TO 13.0	1.4	1.5	6.0
14.0	1.5	1.7	6.0
15.0	1.5	1.7	6.0
16.0 & 17.0	1.7	1.8	7.0
16.0	1.8	2.0	8.0
20.0	1.8	2.0	10.0
22.0	1.8	2.0	12.0

NOTES:

1. POLES TO BE 'STOUT CLASS' TO BS 1990. CREOSOTED TO BS913 BY RUEPING PROCESS, AFTER FABRICATION.
2. POLES TO BE MATCHED FOR H STRUCTURES. EACH PAIR OF POLES TO BE MARKED WITH IDENTICAL PAIRING NUMBERS.
3. MINIMUM POLE TOP DIAMETER 205mm FOR INTERMEDIATES, 215mm FOR SECTION POLES. SCARFING ONLY REQUIRED WHERE POLE TOP DIAMETER EXCEEDS THESE DIMENSIONS.
4. ALL HOLES DRILLED AT RIGHT ANGLES TO VERTICAL CENTRE LINE OF POLE.
5. 1 ADDITIONAL HOLE AT 2440 INTERVAL FOR POLES OVER 14m.
6. ANGLE AND TERMINAL POLES TO HAVE A POLE TOP DIAMETER NOT LESS THAN 20mm ABOVE THE MINIMUM SPECIFIED IN BS 1990 TABLE 3.

DIMENSIONS IN MILLIMETRES

FORMERLY YE DRAWING No. Y204L0601

NORTHERN POWERGRID

Lloyds Court, 78 Grey Street, Newcastle Upon Tyne, NE1 6AF

POLE FABRICATION INTERMEDIATE, ANGLE AND SLACK SPAN TERMINAL CE/C/37M

Manufacturer Details			
Sheet No. 1	Scale 1:20		
Prepared By Barbara.Gordon		Type OVERHEAD POLES	
Revised 01/10/14	Grid Reference	Ref No. C1040653	Historic Drg.No. 1091380011
Date Issued 01/10/14	Checked By G HAMMEL	Revision	Notes