





NOTES

- 1. ALL HOLES SHALL BE 18 mm DIA. WITH THE EXCEPTION OF THE TOP WHICH WILL BE 22 mm DIA.
- 2. HOLES SHALL BE DRILLED TO TEMPLATE, ACCURATE AND DEAD CENTRE.

All dimensions in millimetres

Intermediate Pole LV Lines & Services	© UK Power Networks 2014		
	DRN. June 1994	DRAWING NUMBER	ISSUE
	CKD. January 2014	EDS 01-9000.01	1
	APP.		

**NOTES**


1. ALL HOLES SHALL BE 22mm DIA. UNLESS STATED OTHERWISE.
2. HOLES SHALL BE DRILLED TO TEMPLATE ACCURATE AND DEAD CENTRE.
3. SCARFING SHALL BE CUT TO GIVE A 50mm WIDE FACE AND THE LOWER END CHAMFERED OFF BEYOND THE LENGTH SHOWN.
4. DIMENSION "A" SHALL BE
1000mm FOR POLES UP TO 11m.
1400mm FOR POLES OVER 11m.

All dimensions in millimetres

Intermediate Pole HV/LV Combined Construction Lines

© UK Power Networks 2014

DRN. June 1994	DRAWING NUMBER	ISSUE
CKD. January 2014	EDS 01-9000.02	1
APP.		

**NOTES**


1. ALL HOLES SHALL BE 22mm DIA. UNLESS STATED OTHERWISE.
2. HOLES SHALL BE DRILLED TO TEMPLATE ACCURATE AND DEAD CENTRE.
3. FOR LINE DEVIATION OVER 60°, HOLES FOR L.V. SECTION SHALL BE DRILLED ON SITE MAINTAINING THE 900mm CLEARANCE SHOWN.
THE TWO SETS OF L.V. DRILLINGS SHALL BE 25mm APART AND IN LINE WITH L.V. CONDUCTORS.
4. ADDITIONAL POLE TOP SCARFING FOR LINE DEVIATION OVER 60° SHALL BE DONE ON SITE.
5. SCARFING SHALL BE CUT TO GIVE A 50mm WIDE FACE AND THE LOWER END CHAMFERED OFF BEYOND THE LENGTH SHOWN.
6. DIMENSION "A" SHALL BE
1100mm FOR POLES UP TO 11m.
1400mm FOR POLES OVER 11m.

All dimensions in millimetres

Section Pole HV/LV Combined Construction Lines

© UK Power Networks 2014

DRN. June 1994	DRAWING NUMBER	ISSUE
CKD. January 2014	EDS 01-9000.03	1
APP.		



NOTES


1. ALL HOLES SHALL BE 22mm DIA. UNLESS STATED OTHERWISE.
2. HOLES SHALL BE DRILLED TO TEMPLATE, ACCURATE AND DEAD CENTRE.
3. SCARFING SHALL BE CUT TO GIVE A 50mm WIDE FACE AND THE LOWER END CHAMFERED OFF BEYOND THE LENGTH SHOWN.
4. DIMENSION "A" SHALL BE
1100mm FOR POLES UP TO 11m.
1400mm FOR POLES OVER 11m.
5. HOLES FOR SURGE DIVERTERS TO BE DRILLED ON SITE, WHEN REQUIRED.

All dimensions in millimetres

Terminal Pole HV/LV Combined Construction Lines

© UK Power Networks 2014

DRN. June 1994	DRAWING NUMBER	ISSUE
CKD. January 2014	EDS 01-9000.04	1
APP.		

**NOTES**



1. ALL HOLES SHALL BE 22mm DIA. UNLESS STATED OTHERWISE.
2. ALL HOLES SHALL BE DRILLED TO TEMPLATE, ACCURATE AND DEAD CENTRE.
3. SCARFING SHALL BE CUT TO GIVE A 50mm WIDE FACE AND THE LOWER END CHAMFERED OFF BEYOND THE LENGTH SHOWN.
4. FOR LINE DEVIATION OVER 60° ADDITIONAL POLE TOP SCARFING SHALL BE DONE ON SITE.
5. HOLES FOR SURGE DIVERTERS DRILLED ON SITE WHEN REQUIRED.
6. DIMENSION "A" SHALL BE 1100mm FOR POLES UP TO 11m. 1400mm FOR POLES OVER 11m.

All dimensions in millimetres

Intermediate, Section, Tee-off
or Terminal Pole
HV Light Construction Lines

© UK Power Networks 2014

DRN. June 1994	DRAWING NUMBER	ISSUE
CKD. February 2014	EDS 01-9000.05	1
APP.		



NOTES



1. ALL HOLES SHALL BE 22mm DIA. UNLESS STATED OTHERWISE.
2. ALL SCARFING AND SLOTS, EXCEPT THOSE FOR KICKING BLOCKS, SHALL BE CUT SQUARE TO GIVE A 75mm WIDE FACE.
3. DIMENSION "A" SHALL BE 1400mm FOR POLES UP TO 13m. 1700mm FOR POLES OVER 13m.

All dimensions in millimetres

Intermediate Pole
33kV/HV
Light & Heavy Construction Lines

© UK Power Networks 2014

DRN. June 1994	DRAWING NUMBER	ISSUE
CKD. February 2014	EDS 01-9000.06	1
APP.		



NOTES


1. ALL HOLES SHALL BE 22mm DIA. UNLESS STATED OTHERWISE.
2. ALL HOLES SHALL BE DRILLED TO TEMPLATE, ACCURATE AND DEAD CENTRE.
3. DIAMETER AT POLE TOP SHALL BE 220mm MIN. BEFORE SCARFING.
4. DIMENSION "A" SHALL BE 1400mm FOR POLES UP TO 13m. 1700mm FOR POLES OVER 13m.

All dimensions in millimetres

Section Pole HV Light Construction Lines

© UK Power Networks 2014

DRN. June 1994	DRAWING NUMBER	ISSUE
CKD. February 2014	EDS 01-9000.07	1
APP.		

**NOTES**



1. ALL HOLES SHALL BE 22mm DIA. UNLESS STATED OTHERWISE.
2. ALL HOLES SHALL BE DRILLED TO TEMPLATE, ACCURATE AND DEAD CENTRE.
3. HOLES FOR SURGE DIVERTERS DRILLED ON SITE WHEN REQUIRED.
4. SCARFING SHALL BE SQUARE CUT TO GIVE A 75mm WIDE FACE.
5. DIMENSION "A" SHALL BE 1400mm FOR POLES UP TO 13m. 1700mm FOR POLES OVER 13m.

All dimensions in millimetres

Terminal Pole
33kV/HV
Light & Heavy Construction Lines

© UK Power Networks 2014

DRN. June 1994	DRAWING NUMBER	ISSUE
CKD. February 2014	EDS 01-9000.08	1
APP.		



NOTES



1. ALL HOLES SHALL BE 22mm DIA. UNLESS STATED OTHERWISE.
2. HOLES TO BE DRILLED TO TEMPLATE, ACCURATE AND DEAD CENTRE.
3. DIMENSION "A" SHALL BE
1200mm FOR POLES UP TO 13m.
1500mm FOR POLES OVER 13m.
4. THE TWO LIMBS COMPRISING THE "H" POLE SHALL BE MATCHED BY THE SUPPLIER.

All dimensions in millimetres

Section H Pole, Max Deviation 60° 11/33kV Heavy Construction Lines

© UK Power Networks 2014

DRN. June 1994	DRAWING NUMBER	ISSUE
CKD. February 2014	EDS 01-9000.09	1
APP.		



NOTES



1. ALL HOLES SHALL BE 22mm DIA. UNLESS STATED OTHERWISE.
2. HOLES TO BE DRILLED TO TEMPLATE, ACCURATE AND DEAD CENTRE.
3. THE TWO LIMBS COMPRISING THE "H" POLE SHALL BE MATCHED BY THE SUPPLIER.

All dimensions in millimetres

Section H Pole, Deviation Over 60° 11/33kV Heavy Construction Lines

© UK Power Networks 2014

DRN. June 1994	DRAWING NUMBER	ISSUE
CKD. February 2014	EDS 01-9000.10	1
APP.		



NOTES

1. ALL HOLES SHALL BE 22mm DIA. UNLESS STATED OTHERWISE.
2. HOLES TO BE DRILLED TO TEMPLATE, ACCURATE AND DEAD CENTRE.
3. DIMENSION "A" SHALL BE 1200mm FOR POLES UP TO 13m. 1500mm FOR POLES OVER 13m.
4. THE TWO LIMBS COMPRISING THE "H" POLE SHALL BE MATCHED BY THE SUPPLIER.
5. HOLES FOR SURGE DIVERTERS DRILLED TO ORDER WHEN REQUIRED.

All dimensions in millimetres

Terminal H Pole 11/33kV Heavy Construction Lines

© UK Power Networks 2014

DRN. June 1994

DRAWING NUMBER


ISSUE

CKD. February 2014


EDS 01-9000.11

1

APP.



SINGLE POLE



TWIN POLE

NOTES

1. ALL HOLES TO BE 22mm DIA. UNLESS OTHERWISE STATED, DRILLED TO TEMPLATE, ACCURATE AND DEAD CENTRE.
2. TWIN POLES TO BE MATCHED AND ASSEMBLED AT SUPPLIER'S YARD.
3. POLE TYPE AND DIMENSION 'A' TO BE SPECIFIED. DIMENSION 'A' TO MATCH VERTICAL CONDUCTOR SPACING, i.e. 1200 or 1500mm.
4. DIMENSION 'B' TO BE 1400mm FOR POLES 13m. AND UNDER, 1700mm FOR POLES OVER 13m.
5. SHEAR BLOCKS TO BE WELL SEASONED OAK CUT 50 LONGER THAN SCARFED FACE. SCARFING 12mm DEEP, SQUARE CUT AND DRILLED FOR TWO BOLTS AT POSITIONS SHOWN.
6. BOLTS TO BE FITTED TO ALL HOLES EXCEPT:-
i) 24mm DIA. HOLES (FOR INSULATOR EYE BOLTS)
ii) HOLES MARKED * (FOR KICKING BLOCK FIXING BOLTS)

SHEAR BLOCK SCHEDULE

OVERALL HEIGHT OF POLE	DIMENSION A	TOTAL No.REQ'D
10m TO 12m	1200	8
12m TO 13m	1200	9
13m TO 15m	1200	10
15m TO 17m	1200	11
10m TO 12m	1500	8
12m TO 14m	1500	9
14m TO 16m	1500	10
16m TO 18m	1500	11

All dimensions in millimetres

Vertical Formation Section Pole 11/33kV Heavy Construction Lines

© UK Power Networks 2014

DRN. June 1994	DRAWING NUMBER	ISSUE
CKD. February 2014	EDS 01-9000.12	1
APP.		




1. ALL HOLES SHALL BE 22mm DIA. UNLESS STATED OTHERWISE.
2. HOLES TO BE DRILLED TO TEMPLATE, ACCURATE AND DEAD CENTRE.
3. DIMENSION "A" SHALL BE
1200mm FOR POLES UP TO 13m.
1500mm FOR POLES OVER 13m.
4. THE TWO LIMBS COMPRISING THE
"H" POLE SHALL BE MATCHED BY THE
SUPPLIER.

All dimensions in millimetres

Section H Pole with ABSD
Max. Deviation 60°
33kV Heavy Construction Lines

© UK Power Networks 2014

DRN. June 1994	DRAWING NUMBER	ISSUE
CKD. February 2014	EDS 01-9000.13	1
APP.		



NOTES


1. ALL HOLES SHALL BE 22mm DIA. UNLESS STATED OTHERWISE.
2. HOLES TO BE DRILLED TO TEMPLATE, ACCURATE AND DEAD CENTRE.
3. THE TWO LIMBS COMPRISING THE "H" POLE SHALL BE MATCHED BY THE SUPPLIER.

All dimensions in millimetres

Section H Pole with ABSD Deviation Over 60° 33kV Heavy Construction Lines

© UK Power Networks 2014

DRN. June 1994	DRAWING NUMBER	ISSUE
CKD. February 2014	EDS 01-9000.14	1
APP.		



NOTES


1. ALL HOLES SHALL BE 22mm DIA. UNLESS STATED OTHERWISE.
2. HOLES TO BE DRILLED TO TEMPLATE, ACCURATE AND DEAD CENTRE.
3. DIMENSION "A" SHALL BE 1200mm FOR POLES UP TO 13m. 1500mm FOR POLES OVER 13m.
4. THE TWO LIMBS COMPRISING THE "H" POLE SHALL BE MATCHED BY THE SUPPLIER.
5. WHEN SURGE DIVERTERS ARE USED, ADDITIONAL SCARFING TO BE AS SHOWN FOR ONE POLE, BUT ON REVERSE SIDE FOR OTHER POLE, AND HOLES DRILLED AS SHOWN.

All dimensions in millimetres

Terminal H Pole with Droppers 33kV Heavy Construction Lines

© UK Power Networks 2014

DRN. June 1994	DRAWING NUMBER	ISSUE
CKD. February 2014	EDS 01-9000.15	1
APP.		



NOTES



1. ALL HOLES SHALL BE 22mm DIA. UNLESS STATED OTHERWISE.
2. HOLES TO BE DRILLED TO TEMPLATE, ACCURATE AND DEAD CENTRE.
3. DIMENSION "A" SHALL BE 1200mm FOR POLES UP TO 13m. 1500mm FOR POLES OVER 13m.
4. THE TWO LIMBS COMPRISING THE "H" POLE SHALL BE MATCHED BY THE SUPPLIER.
5. WHEN SURGE DIVERTERS ARE USED, ADDITIONAL SCARFING TO BE AS SHOWN FOR ONE POLE, BUT ON REVERSE SIDE FOR OTHER POLE, AND HOLES DRILLED AS SHOWN.

All dimensions in millimetres

Terminal H Pole with Droppers Large Deviation 33kV Heavy Construction Lines

© UK Power Networks 2014

DRN. June 1994	DRAWING NUMBER	ISSUE
CKD. February 2014	EDS 01-9000.16	1
APP.		



NOTES



1. ALL HOLES SHALL BE 22mm DIA. UNLESS STATED OTHERWISE.
2. HOLES TO BE DRILLED TO TEMPLATE, ACCURATE AND DEAD CENTRE.
3. DIMENSION "A" SHALL BE 1200mm FOR POLES UP TO 13m. 1500mm FOR POLES OVER 13m.
4. THE TWO LIMBS COMPRISING THE "H" POLE SHALL BE MATCHED BY THE SUPPLIER.

All dimensions in millimetres

Terminal H Pole with Single Cable Circuit 33kV Heavy Construction Lines

© UK Power Networks 2014

DRN. June 1994	DRAWING NUMBER	ISSUE
CKD. February 2014	EDS 01-9000.17	1
APP.		



NOTES



1. ALL HOLES SHALL BE 22mm DIA. UNLESS STATED OTHERWISE.
2. HOLES TO BE DRILLED TO TEMPLATE, ACCURATE AND DEAD CENTRE.
3. DIMENSION "A" SHALL BE 900mm FOR POLES UP TO 13m. 1200mm FOR POLES OVER 13m.
4. THE TWO LIMBS COMPRISING THE "H" POLE SHALL BE MATCHED BY THE SUPPLIER.

All dimensions in millimetres

Terminal H Pole with Two Cable Circuits 33kV Heavy Construction Lines

© UK Power Networks 2014

DRN. June 1994	DRAWING NUMBER	ISSUE
CKD. February 2014	EDS 01-9000.18	1
APP.		

**NOTES**



1. ALL HOLES SHALL BE 22mm DIA. UNLESS STATED OTHERWISE.
2. HOLES TO BE DRILLED TO TEMPLATE, ACCURATE AND DEAD CENTRE.
3. THE TWO LIMBS COMPRISING THE "H" POLE SHALL BE MATCHED.
4. DIMENSION "A" SHALL BE 1200mm FOR POLES UP TO 13m. 1500mm FOR POLES OVER 13m.

All dimensions in millimetres

Terminal H Pole with ABSD and Single Cable Circuit 33kV Heavy Construction Lines

© UK Power Networks 2014

DRN. June 1994	DRAWING NUMBER	ISSUE
CKD. February 2014	EDS 01-9000.19	1
APP.		



NOTES

1. ALL HOLES SHALL BE 22mm DIA. UNLESS STATED OTHERWISE.
2. HOLES TO BE DRILLED TO TEMPLATE, ACCURATE AND DEAD CENTRE.
3. DIMENSION "A" SHALL BE
1200mm FOR POLES UP TO 11m.
1500mm FOR POLES FROM 12m. TO 16m.
1800mm FOR POLES OVER 16m.
4. THE TWO LIMBS COMPRISING THE "H" POLE SHALL BE MATCHED BY THE SUPPLIER.

All dimensions in millimetres

Intermediate H Pole 33kV Double Circuit Lines

© UK Power Networks 2014

DRN. June 1994

DRAWING NUMBER


ISSUE

CKD. February 2014

EDS 01-9000.20

1


APP.




1. ALL HOLES SHALL BE 22mm DIA. UNLESS STATED OTHERWISE.
2. HOLES TO BE DRILLED TO TEMPLATE, ACCURATE AND DEAD CENTRE.
3. DIMENSION "A" SHALL BE
1200mm FOR POLES UP TO 11m.
1500mm FOR POLES FROM 12m. TO 16m.
1800mm FOR POLES OVER 16m.
4. THE TWO LIMBS COMPRISING THE
"H" POLE SHALL BE MATCHED BY THE
SUPPLIER.
5. WHERE POLE DIAMETERS AT CROSSARM
POSITIONS ARE 225mm OR LESS, THE
SCARFING AT THESE POSITIONS SHALL
BE OMITTED.

© UK Power Networks 2014

DRN. June 1994	DRAWING NUMBER	ISSUE
CKD. February 2014	EDS 01-9000.21	1
APP.		



TYPE B




TYPE C

NOTE
All holes 22mm Dia.


All dimensions in millimetres

Wood Kicking Blocks


© UK Power Networks 2014		
DRN. June 1994	DRAWING NUMBER	ISSUE
CKD. January 2014	EDS 01-9000.22	1
APP.		



TYPE B



TYPE C




TYPE D

NOTE
All holes 22mm Dia.

All dimensions in millimetres

Wood Brace Blocks

© UK Power Networks 2014		
DRN. June 1994	DRAWING NUMBER	ISSUE
CKD. January 2014	EDS 01-9000.23	1
APP.		




Single Pole Fabrication

(Based on ENA TS 43-40, Drg. 434001)

© UK Power Networks 2013

DRN. R.D.H. 15~03~10	SPECIFICATION DRAWING NUMBER	ISSUE
CKD.	EDS 01-9000.101	1
APP.		



NOTES

1. Class of pole to be 'MEDIUM', 'STOUT' or 'EXTRA STOUT' as specified.
2. 'MEDIUM' class poles to have minimum dia. of 175mm at top.
'STOUT' class poles to have minimum dia. of 210mm at top.
3. Poles to be matched.
4. All holes to be 22mm dia. drilled at right angles to vertical centre line of pole. All drilling and cutting to be done strictly to template prior to preservative treatment.
5. Pole butt to be cut at right angles to axis of pole.
6. Pole to be notched and drilled for duplicate 250 x 125 baulks.

POLE LENGTH (m)	DIM. 'X' (mm)
8.5 - 11 Inclusive	1900
11.5 - 12 Inclusive	1700
13 - 15 Inclusive	1400
16 - 18 Inclusive	1100
20 -	500


All Dimensions are in Millimetres

'H' Pole Fabrication

(Based on ENA TS 43-40, Drg. 434002)

© UK Power Networks 2013

DRN.	R.D.H. 15~03~10	SPECIFICATION DRAWING NUMBER	ISSUE
CKD.		EDS 01-9000.102	1
APP.			



DRILLINGS AND MARKINGS

- I. All holes shall be 22mm dia. unless otherwise stated
- II. 75 x 6 x 6mm gouge mark 3000mm up from butt
- III. Butt to be sawn-off square to the axis of the pole
- IV. Pole to be marked as shown
- V. It is essential that the drillings are drilled to template, are accurate and dead centre
- VI. The following information to be impressed on the end grain of butt of pole:
 - (a) Length and diameter of pole
 - (b) Pole number in accordance with schedule

NOTE: The personal mark of the pole inspector will be impressed on the butt

TYPICAL MARKINGS FOR WOOD POLES


- 11 Length of pole in metres
- 300 Diameter of pole in millimetres at 1500mm from the butt
- IF Species code
- 94 Year of impregnation
- @ Name or mark of creosoting firm
- Text to be 25mm high

33kV Single Circuit Intermediate Pole

Based on EPN drawing 4/B1000

© UK Power Networks 2013

DRN. RDH 24.06.94	SPECIFICATION DRAWING NUMBER	ISSUE
CKD.		
APP.	EDS 01-9000.103	1



DRILLINGS AND MARKINGS

- I. All holes shall be 22mm dia. unless otherwise stated
- II. 75 x 6 x 6mm gouge mark 3000mm up from butt on inside of legs
- III. Butt to be sawn-off square to the axis of the pole
- IV. Pole to be marked as shown
- V. It is essential that the drillings are drilled to template, are accurate and dead centre
- VI. Legs of 'H' poles to be carefully matched
- VII. The following information to be impressed on the end grain of butt of pole:
 - (a) Length and diameter of pole
 - (b) Pole number in accordance with schedule

NOTE: The personal mark of the pole inspector will be impressed on the butt

TYPICAL MARKINGS FOR WOOD POLES


- 11 Length of pole in metres
- 300 Diameter of pole in millimetres at 1500mm from the butt
- IF Species code
- 94 Year of impregnation
- @ Name or mark of creosoting firm
- Text to be 25mm high

33kV Single Circuit 'H' Through Pole

Based on EPN drawing 4/B1001

© UK Power Networks 2013

DRN. RDH 17.12.13	SPECIFICATION DRAWING NUMBER	ISSUE
CKD.		
APP.	EDS 01-9000.104	1



33kV Single Circuit Angle/Section Pole

Based on EPN drawing 4/B1002

© UK Power Networks 2013

DRN. RDH 17.12.13

CKD.


APP.

SPECIFICATION
DRAWING NUMBER

EDS 01-9000.105

ISSUE

1



33kV Terminal 'H' Pole

Based on EPN drawing 5/B1007

© UK Power Networks 2013

DRN. RDH 18.12.13

CKD.


APP.

SPECIFICATION
DRAWING NUMBER

EDS 01-9000.106

ISSUE

1



33kV Double Circuit (Unearthed) Intermediate Pole

Based on EPN drawing 4/B1093

© UK Power Networks 2013

DRN. RDH 20.12.13	SPECIFICATION DRAWING NUMBER	ISSUE
CKD.	EDS 01-9000.107	1
APP.		